

Prefabricated Construction Systems for Building and Civil works

adopted in Hong Kong

Presented by

Raymond W M Wong

Division of Building Science & Technology

City University of Hong Kong

The presentation is based on a paper prepared
by Raymond Wong for the

World Congress on Housing Process & Product,

Organized by the International Association for Housing Science
and hosted by the Concordia University,

Montreal, Canada, June 2003

Development and Application of Prefabricated Technology in Building Construction in HK

1. Had been used once in early 1970s in a pilot project to construct a series of 17-storey public houses
2. Used in a broader scale in the mid/late 1980s in the construction of public houses where all the façades of the flats were constructed in precast in a after-fixed manner
3. Improvement to public houses by introducing in-situ joined façade and broader use of other precast elements in early/mid 1990s.
4. A few private developments pioneered in the use of prefabricated system in the construction of buildings of various nature since early 1990s

Development and Application (continue)

5. Packaged projects introduced from late 1990 onward by the Hong Kong government for the construction of a series of schools using semi-prefabricated method
6. A series of government quarter buildings using similar construction techniques were introduced in 2000
7. A few special buildings such as bus depot or train station podium employed large amount of prefabricated elements of which some were primary structural members (1997 onward)
8. Popular use of prefabricated external wall from 2002 onward in residential buildings due to the introduction of a new guideline encouraging the use of precast façades as a form of green elements in construction (exemption of Gross Floor Area)

Generations of Public Houses
(Harmony Block) constructed
using semi-prefabricated concept

First generation of Harmony Block using after-fix façade



Later version of Harmony Block using in situ façade cast at the same time with structural walls



Precasting yard was set up to produce precast elements for public housing projects in early to mid 1990



After-fix façade system required the formation of small amount of in-situ joint and grouting that easily caused leaking problem





Detail of façade installation using in-situ jointing arrangement in the later version of Harmony Block Construction





Forming the floor slab in the Harmony Block construction using semi-slab (right) and aluminium formwork (above)

Introduction of mechanical formwork systems incorporating the standard precast elements in the construction of latest version of public houses in the late 1990





Public houses using Concord design with special emphasis on the use of mechanicalised construction system

Layout of the Concord Block showing the position of the cast-in-situ core wall, shear walls and precast façade


Block 2
Option 7

WING D
Stage-4




WING C
Stage-3

WING A
Stage-

WING B
Stage-2



DIMENSION OF DOOR OPENING

	HEIGHT	WIDTH
	2175	1550
	2300	1400
	2150	850

Other pioneered projects in the
early 1990 constructed using
semi-prefabricated concept



The construction of the Headquarter and Members Facilities Complex for the Hong Kong Jockey Club



Forming the floor slab using precast secondary beams and semi-slab for the main building (above) and members' complex (right)



Detail of the floor system with the cast in-situ main beams and the place-in precast secondary beams

Introduction of prefabricated
concept to construct government
quarters in 2000



Government quarters
in West Kowloon



Layout of the quarter building showing typical phasing arrangement of work



Features in the construction –
extensive use of precast
façade and lintel beams,
precast cast-in-situ internal
partitions are also introduced



Detail of the façade and the lintel beam installation



Installation of the cast-in-situ precast internal partition



Construction of special buildings
using high proportion of precast
since 1998

Kowloon Canton Railway
Station podium/deck



Construction of the Kowloon
Canton Rail podium deck –
cargo handling bay on the
ground level and on top for a
large-scale residential
development afterward





Forming of the cast-in-situ main beams



Joining detail of the main beam and precast secondary beams



Semi-slab with RC topping to form the composite podium deck



Kowloon Motor Bus Maintenance Depot

- 3-level depot building with columns, main and secondary beams all in precast





Erecting of the building frame
using precast columns and beams



Connecting the precast column to the foundation cap with a base plate

Placing the secondary beams onto the main beam



Connecting beams to columns by stitching, a means to provide an in-situ joints with rigid RC links





Detail of the beam/column
and beam/beam joints



Recent Residential/Commercial
Developments using prefabricated
concept to construct



Residential development
at Cyber Port



Façade and general installation details



Features in the construction – large amount of external walls are constructed in precast façade units, with major structural links tie back to the inner shear walls and floor slab



Incorporation of other sophisticated formwork in construction – steel gang form for walls and table form for floor





Residential Development at Taikoo Valley

Construction features – the use of large amount of precast units both of structural or architectural nature. This includes the balcony, façade units, loss-form for external walls and some shading fins.

Detail of the precast balcony unit



Detail of the loss-form





Residential development
at Ma Tau Wai





Overview of the precast installation arrangement





Façade installation detail
as seen on the floor deck



Cambridge House – a 42-storey
Office Building at Quarry Bay



Features in construction –
precast beam trough and
precast sub-slab with RC
topping forming the floor system



Placing of the precast beam trough
to form the floor layout



Recent Achievements of Hong Kong's Prefabricated Technology

- Previous defects such as leakage problems have been improved
- Application diversified to other forms of construction
- Capable to apply to rather complicate-shaped buildings
- Incorporation of other advanced technology in the construction (such as use with mechanical form/ tensioned elements)
- Generally mastering of skill and growing popular

Future Trend in the application of Prefabricated Technology in Hong Kong

1. To increase the use of prefabrication for more structural elements such as for beam, column or load bearing wall
2. Use more modulated elements or plug-in units
3. Use more for architectural or decorative elements
4. Incorporation of other composite elements in the design such as using at the same time with structural steel
5. Apply prefabrication more to medium-rise buildings with more standardized structural items
6. Improve the supply chain management to make production more efficient and economical

Practical Constraints

1. Tighter coordination to allow for structural design, construction planning, procurement & approval procedure
2. Required a critical amount of precast items before work can be economically used
3. Huge work space for handling precast elements especially in congested urban environment in Hong Kong
4. Congested site environment makes access and delivery of heavy precast units to the work spot becomes difficult
5. Quality assurance become critical especially where large amount of precast components are used as structural nature

Examples of very congested construction environment where prefabrication approach is adopted





Example of Innovative Project (Local)

The Integer



The Integer House
at Admiralty






Floor plan of the experimental house



The working concept




Typical connection details



Assembly of the 3-D modules



Possible future development for high-rise structures using similar concept




Example of Innovative Project (overseas)

The Habitat 67 in Montreal, Canada



Habitat 67 as seen along the bank of St Lawrence River



Habitat 67 as seen along the bank of St Lawrence River

Close up look of the modulated dwelling units




Close up look of the modulated dwelling units and the linking structure in the form of a access corridor





View as seen on
the deck level






Forming and Installation of the modulated units




Installation of the modulated units and the associated structure

Building Section



Section through structure showing modular house with gardens, pedestrian streets, and the mechanical and electrical distribution.





Floor plan

Connecting the modules



Prefabricated Construction

Application in Civil Works

Examples of application of prefabricated techniques in civil construction works

1. Used in highway projects such as cantilevered deck of elevated bridge, parapets of expressway and road curb
2. Precast girder units or beams for elevated roadway (viaduct)
3. Precast beams or decks for elevated pedestrian footbridges
4. Tunnel lining especially for tunnel formed by tunnel boring machine
5. Decks for long span bridges

Examples of application (continue)

6. Marine work such as seawall and deck of terminal berth
7. Soil retaining element such as for earth-balanced type retaining structure
8. Platform for railway station
9. Parapets and noise barrier panels
10. Overhanging ducts or services channels for underground facilities
11. Nullah section for storm water discharge



Elevated pedestrian footbridge in Mong Kok



Piers formed using
precast column






Precast girder erected
on top of the piers to
form the main span of
the footbridge




Extending precast plank to form the deck of the footbridge





Structural arrangement of the footbridge





Precast V-shape beam
for the Route 3
elevated expressway
at Kwai Chung

Precast V-shape beam
being lifted to pier head
by launching gantry



Precast box-girder for the Rambler Strait Bridge of Route 3





Forming the elevated bridge of the West Kowloon Expressway



West Kowloon Expressway –
installing the precast box girder using
balanced cantilever method with the
help of track mounted gantry crane



Forming the elevated track of the West Rail using the slung launching girder



Forming the elevated track of the West Rail using the longitudinal steel support beam



Forming the elevated track of the KCR Ma On Shan Line by precast girder and lifted to deck level for erection using mobile crane


Placing the precast girder in position



Project example – Road T7 in Ma On Shan (TTD project)

Technical Features

1. Total length of viaduct – 2200m (approx.)
2. Span length – Average 40m
3. Total nos. of segment used – 790 nos.
4. No. of segment per span – average 14 nos.
5. Weight of segment – ranging from 50 to 98 tons
6. Weight of the launching machine – 310 tons
7. Max. weight of machine with segments – 1300 tons
8. Length of launching machine – 85m
9. Casting of the box-girder segment – match-cast



Construction of highway bridge using precast box-girder (viaduct) – Road T7 in Ma On Shan



Early stage of the project –
formation and forming the
piers for the viaduct



Overall layout of the precasting yard





Forming the box-girder units



Formwork to form the inner void of the box-girder units

Overview of the
launching machine





Drawing provided by
China Harbour Engg.
Co. (Group)

Launching sequence of the box-girder units using launching machine



Installation of the box-girders



Installation of the box-girders

Precast parapet unit for the highway and railway road/track way





Precast floating slab for the laying of railway track

Tunnel lining formed
by precast segments





Detail of the lining as
seen inside the tunnel tube



Forming the station platform using precast curb and plank (KCR Tsim Sha Tsui Station)




Forming the cable hood



Delivery of the precast units



Forming the deck of the Ting Kau Bridge using precast concrete plank



Forming the deck of the berth for the Container Terminal No. 9



Precast concrete plank
as cover to podium deck

Precast vertical panel forming an earth-reinforced type retaining structure





Forming storm water discharge culvert – Tseung Kwan O Reclamation



Delivery and storage along the temporary seawall

Prepare for the foundation to support the culvert



Precast units to form the 4m high 5-cell culvert system in Tseung Kwan O

Positioning the Precast units onto the culvert alignment



Precast culvert in the form
of semi-submerged tube –
Tsuen Wan West
Reclamation as advanced
work for the West Rail
Tsuen Wan Station



Sinking of the precast
culvert section



Positioning of the culvert section onto to formed bed



Connecting the culvert from the precast section to the in-situ section





Precast box as footing to bridge tower – Tsing Ma Bridge tower on Ma Wan side

Precast box as pump house
for water cooling system in
the Central Reclamation



End of Presentation and Thank you

If you require more information about the
Author's recent work on various
technology topics, you can enter his
homepage at

<http://personal.cityu.edu.hk/~bswmwong/>